

RADCON  
PLAN

RADIOLOGICAL CLEANUP PLAN FOR ENEWETAK ATOLL

(D R A F T) #2

16 January 1976

Field Command, Defense Nuclear Agency

**E E E E E L L L L L L L L L L L L L L L L**

# RADIOLOGICAL CLEANUP PLAN FOR ENEWETAK ATOLL

	<u>PAGE</u>
I. PURPOSE. . . . .	1
II. SOIL CLEANUP . . . . .	2
A. General. . . . .	2
B. Pu Suspect Areas . . . . .	3
C. Sampling Methods . . . . .	4
D. Sampling Preparation . . . . .	5
E. Pu Analysis. . . . .	5
F. Pu Cleanup Areas . . . . .	6
G. Cleanup. . . . .	7
H. Ranking. . . . .	8
III. DEBRIS CLEANUP . . . . .	9
A. General. . . . .	9
B. Criteria . . . . .	10
C. Procedures . . . . .	12
IV. RADIATION SAFETY . . . . .	14
A. General. . . . .	14
B. Applicability. . . . .	14
C. Controlled Areas . . . . .	15
D. Radiation Protection Standards . . . . .	15
E. Medical Examinations . . . . .	16
F. Training . . . . .	17
G. Personnel Dosimetry. . . . .	18
H. Protection Clothing. . . . .	18
I. Decontamination. . . . .	21

- Enclosure 1. Schedule of Initial Soil Sampling for Enewetak Cleanup
- Enclosure 2. Enewetak Islands to be Searched
- Enclosure 3. Radiation Protection Standards for Cleanup

## RADIOLOGICAL CLEANUP PLAN FOR THE ENEWETAK ATOLL

### I. PURPOSE

This Plan serves as the basis on which the radiological cleanup of Enewetak Atoll will be conducted. (Nonradiological cleanup is included only where necessary to differentiate the two.) The Plan attempts to structure a cleanup which incorporates the AEC Task Group Recommendations and other established radiation principles and practices with engineering methods and technology available for cleanup within the major constraint of limited funds authorized by the Congress. It covers the cleanup of contaminated soil and debris in accordance with the Environmental Impact Statement, and the radiation safety necessary to accomplish these endeavors in a satisfactory manner. Following approval of this Plan, detailed Standing Operating Procedures (SOPs) will be prepared as necessary.

## II. SOIL CLEANUP

### A. GENERAL.

1. The only contaminated soil to be removed as part of Cleanup is that which is contaminated with plutonium and its decay products. A basic assumption of the Cleanup Plan is that the AEC Enewetak Radiological Survey (AEC Report NVO-140, Oct 73) located all significant areas of such contamination. The Survey did not investigate every "square inch" of the Atoll; however, a random-sampling method was employed which was biased to increase sampling frequency in areas suspected of being contaminated because they were previously surface ground zeros and/or in fallout patterns, and in areas which were considered likely to be inhabited someday. Sufficient samples were taken and analyzed from other areas such that the probability of any significant "hot spots" being missed is considered negligibly small. In other words, the Survey will be accepted as an authoritative source for having identified all areas potentially requiring plutonium-contaminated soil removal and no additional areas or "hot spots" are expected nor will any be searched for intentionally. Only if additional evidence is forthcoming will other areas be investigated for plutonium contamination.

2. Areas will be investigated as potentially requiring soil Cleanup only if the Survey reported them to have plutonium at concentrations greater than 40 pCi/g. Further, the numerical concentration values reported in NVO-140 will be the deciding factor irregardless of

sample dimensions or configuration. Thus, for example, samples which were 10-cm thick will be considered equally with samples which were 15-cm thick if they both were reported to have the same plutonium concentrations. Accordingly, islands or portions of islands which the Survey showed to have plutonium at less than 40 pCi/g will ~~not be investigated~~. ✓  
①

*have the head of one of will look after places as*  
B. PU SUSPECT AREAS. *resources from + add documentation*  
*of the low level (10 pCi/g) from a*  
*technical standpoint*

1. Enclosure 1 differentiates those islands and portions of islands which might require soil removal from those which will definitely not require soil removal. (Approval of this Plan by ERDA is tantamount to a certification that the islands and portions of islands excluded from cleanup according to Enclosure 1 do not have plutonium contamination; namely, 40 pCi/g.) Without strong and new evidence to the contrary, only the areas designated for sampling in Enclosure 1 will be investigated. These areas will be referred to henceforth as "Pu suspect areas." 7

*Sampling of*  
2. <sup>with</sup> Pu suspect areas will be ~~sampled at the locations specified~~ *begin at the plan*  
*advising that changes may occur as data is collected.*  
in Enclosure 1. Each Pu suspect area will be surveyed to establish the horizontal coordinates and elevations of locations to be sampled. These sample locations will be uniquely marked so that on subsequent visits to a Pu suspect area the sampling locations can be readily identified. For areas having dense or tall vegetation that might interfere with survey-

ing and sampling, paths will be made. In so doing, vegetation will be removed with the least possible disturbance to the underlying soil; e.g., brush will be mowed down by either manual or mechanical means which attempt to leave root structures intact. Any brush which is cut will be collected and removed from the Pu suspect area and mechanically chopped to make mulch. All vegetation thus removed will be assumed to be noncontaminated with plutonium, but will be treated respectfully as though it might contain other radioactive contaminants. Accordingly, it will not be burned.

*note*  
3. ~~PIDLER~~ readings will be made while the soil sampling is being performed. Locations which give a clear plutonium response will be documented (by the surveyors) along with the reading.

#### C. SAMPLING METHODS.

1. Samples will be taken at either the air-ground interface (surface) or at depths beneath the interface (profile). Surface samples will be obtained by using a "top-soil cutter" tool which will facilitate removing sod to a depth of 5 cm within a well-defined area. The cutter area (or total area sampled) will be sufficient to give a sample mass which can be analyzed for plutonium by gamma spectroscopy (absolute counting of Am-241 gammas) down to the 40 pCi/g range. The mass is to be determined but probably will be in the order of 0.5 kg. Profile sam-

ples will be obtained by digging a trench immediately adjacent to the area to be sampled and removing soil from the trench wall by pushing into it a square pan with cutting edges on one open side. The pan will have a top-to-bottom distance of 5 cm and total mass collected will be the same as with surface samples.

2. Sample locations will be described; e.g., location is open savannah, brush-covered, or forested, and level, mounded or depressed, as such information might provide additional clues for defining the bounds of cleanup areas.

*3. Other techniques may prove useful in gathering more information.*

#### D. SAMPLE PREPARATION.

Samples will be prepared for gamma spectroscopy by breaking up aggregates and pulling apart topsoil plugs (consisting of vegetation and root mat) as necessary. Any vegetation will be cut up so that it can eventually be distributed homogeneously. Samples will be dried sufficiently to allow successful mixing. Except for large rocks, which will be separated and discarded without taking any special efforts to remove surface deposits, the entire sample will be blended to give a more-or-less homogeneous matrix. A weighed quantity of the mixed sample will be packed into a standard-size container for analysis.

#### E. PU ANALYSIS.

1. Plutonium assay will be by nondestructive analysis whenever possible, employing high-resolution gamma-ray spectrometers with either intrinsic or lithium-drifted germanium detectors. The 64 keV gamma ray from the decay of Am-241 will be the indicator of plutonium. The counting system will be calibrated with Am-241-spiked soil samples equivalent to plutonium concentrations covering the range of interest, say 10 to 2000 pCi/g. The activity ratio of Am-241/Pu-239 will be assumed to be 0.4 as reported in NVO<sup>149</sup>, pg 97. In determining the total Pu activity, the Pu-238/Pu-239 ratio of 0.1 will be used, and no other Pu isotopes will be considered. Each sample will be analyzed (counted) once for a specified time, on the order of 50 minutes.

2. For samples whose Pu concentration is deemed critical to the conduct of Cleanup, analysis will be by standard radiochemical means using an acid-extraction, electro-deposition of unknown plutonium with tracer, and counting by alpha spectrometry.

#### F. PU CLEANUP AREAS.

Sample analyses will be correlated with survey data, any on-site FIDLER readings and qualitative observations. If no samples yield Pu concentrations greater than 40 pCi/g, the Pu suspect area will be considered as noncontaminated and certified to be clean. If any positive readings (greater than 40 pCi/g) are obtained, they will either indicate



areas to be sampled in greater detail or will serve to define areas potentially (see Cleanup ranking below) to be cleaned. If more data is deemed necessary in order to better define cleanup areas, the survey/sampling process described above will be repeated.

#### G. CLEANUP.

1. The border of areas to be cleaned will be marked by surveyors. The entire enclosed area will then be devegetated in the manner which causes the least disturbance to underlying soil. Mowed vegetation will be removed for mulching. Easily removable contaminated and noncontaminated debris will also be taken away (see Part III B Criteria). Large structures and concrete slabs which likely were in place prior to the deposition of any plutonium and which do not interfere with Cleanup will not be removed unless "swipes" show excessive removable plutonium is present.

2. For those Pu-contaminated areas which have highest concentrations near the air-ground interface (the majority of the Pu suspect areas), the soil will be removed in thin layers, one layer at a time, to a depth of at least 15 cm. The layers of soil and root mats will be assembled at central collection points, loaded into open bed trucks, covered and transported to the ultimate disposal site.

3. For Pu-contaminated areas which have high Pu concentrations at great depths, soil will be removed in conveniently thick layers until approaching the required excavation limits, then they will be removed in thin layers as described above.

4. Cleanup areas will be sampled at some to-be-determined frequency during soil removal operations to permit decisions on removing additional soil or certifying the area as cleaned. The scraping/sampling will be repeated iteratively, presumably reducing the area for cleanup with each pass, until an acceptable level has been reached. The endpoint to Cleanup at any site will be when plutonium concentration is assuredly below 40 pCi/g according to the gamma spectroscopy counting method employed. Areas that ERDA certifies as clean will subsequently be sown with grass seed.

#### H. RANKING.

The Pu suspect areas together encompass an area of approximately 150 acres. This total is probably on the high side, however, as suspect area bounds were liberally placed. As summarized in Enclosure 1, nearly 4,000 samples are initially programmed for analysis to ~~eliminate the~~ ~~suspicious~~ and define the areas deserving Cleanup. The last column in Enclosure 1 summarizes an attempt to estimate the quantity of material which would be excised if the entire 150 acres must be cleaned up. The volumes were calculated by assuming that areas with significant contamination at the surface only will require cleanup to a depth of 15 cm, and areas which are contaminated to greater depths will be cleaned up to a depth approximately at the point where the AEC Survey shows Pu con-

centration to decrease to 40 pCi/g. The total volume according to these estimates is about 120,000 cubic meters (157,000 cubic yards). As such quantities might exhaust resources available, contaminated areas will be ranked following their initial definition. The ranking will consider factors such as the depth of burial, Pu distribution in each area, range and absolute values of concentrations, time and efforts required to perform soil removal, location of areas, etc, and will be negotiated with the ERDA Representative. The areas will be cleaned up according to their ranking. 144/5  
150/100

### III. DEBRIS CLEANUP

#### A. GENERAL

1. The AEC Task Group recommended that "all radioactive scrap metal and contaminated debris now or later identified" should be removed from Enewetak Atoll as part of Cleanup. Holmes & Narver, Inc, made the initial identification (H&N-1348) based on radiation measurements made during a brief two-week period of the Engineering Survey (12 Oct-21 Dec 72) by monitorings from the EPA working under the direction of the AEC. The Cleanup EIS estimates that materials identified as contaminated in H&N-1348 occupy a total volume of 7,262 cubic yards.

2. The two-week contaminated debris survey was limited to the detection of gamma contamination (alpha and beta contamination were not sought) present on the ten islands which had either surface ground zeros or heavy, close-in fallout. Additionally, only structures and scrap which were on the surface, visible and accessible were inspected, and no

attempt was made to search for structures not shown on as-built drawings. Thus, although H&N-1348 lists about 400 items of debris for the ten islands, the AEC (in report NVO-140) reports radiation measurements for only half of them (about 190 items).

3. The AEC did not establish any criteria for designating debris as contaminated. NVO-140 merely reports a single gamma exposure rate (presumably the highest) for the general area of an item of debris. Thus, for example, a "scattered junkpile" on Alice is given a value of 120mR/h and without any indication of the quantity of junk which has that exposure rate or whether any of the junk should be labeled as contaminated or noncontaminated. Cleanup will make the differentiation by comparison against specific criteria.

#### B. CRITERIA

1. No material is totally devoid of radioactivity. However, not every material should be considered as a radioactive pollutant worthy of decontamination. Some level of radioactivity below which a material should not be regarded as "contaminated" is proper. This is particularly appropriate at Enewetak since the general background to remain after Cleanup will in many places be greater than the radiation level from any individual item. No Federal or International rules and regulations are directly suitable for Cleanup, so this Radiological Plan will promulgate criteria for Cleanup.

2. The AEC Task Group and the Cleanup EIS note that materials which might be used by people in place or removed for use elsewhere are the ones of concern. Since there are post-Cleanup constraints on use of

"contaminated" organic materials (plants and animals), the Cleanup materials available for differentiation (contaminated or noncontaminated) are metal and concrete. These materials will collectively be called "debris."

3. The radioactivity of debris can be removable surface contamination or fixed (nonremovable) contamination either on the surface or distributed throughout, as might result from activation. Cleanup will assume that any alpha radioactivity is present only as removable contamination, beta radiation is the predominant fixed contamination of concrete debris, and gamma radiation is the predominant fixed contamination of metallic debris.

4. Debris will be considered as contaminated and programmed for radiological Cleanup if it gives either:

(a) to a filter-paper swipe over a  $100\text{cm}^2$  area, an alpha radiation disintegration rate  $\geq 20$  dpm;

(b) an absorbed dose rate  $\geq 100$   $\mu\text{rad/h}$  when measured at a one cm distance through not more than seven  $\text{mg/cm}^2$  absorbing material;  
or

(c) an exposure rate  $\geq 15$   $\mu\text{R/h}$  at a 30 cm distance.

## C. PROCEDURES

1. Cleanup will assume that the only islands which might have contaminated debris are those listed in Enclosure 2 (Approval of this Plan by ERDA is tantamount to a certification that the islands excluded from Enclosure 2 do not have contaminated debris.) These islands comprise about 900 acres including the 150 acres to be investigated for soil Cleanup. The entire 900 acres will be searched for debris, and all which is found will be monitored for classification according the above contamination criteria. The search will include thinning over-grown areas as necessary to permit a visual search for concrete and metallic debris. The only buried debris to be investigated will be at locations reported to be radioactive material burial sites.

2. Each item of debris will be filter-paper swiped and large items will be swiped at least once for every 10 m<sup>2</sup> of exposed surface.

The swipes will be counted for alpha radiation. Exposed surfaces of concrete debris will be monitored for beta/gamma radiation according to criterion in para III.B.4(b) at a frequency of at least one reading for every square meter. Metallic debris will be thoroughly monitored for gamma radiation according to criterion in para III.B.4(c). All debris which qualified as "contaminated" will be uniquely marked for disposal.

The noncontaminated debris will also be marked but disposed of only if it poses a physical hazard or is an obstruction to intended use of the site on which it is located. Records will be maintained of radiation readings for each item.

3. Contaminated debris will be collected and loaded in open-bed trucks <sup>(contaminated)</sup> for transport by barge to the disposal site. The trucks will be monitored to assure that the absorbed dose rate at no point on the external surface exceeds 0.5 mrem/h. Any contaminated debris which might cause this limit to be exceeded will be separated and safely packaged for transport. Debris for Cleanup that is not contaminated as defined herein will be disposed of as noncontaminated debris regardless of any residual contamination it might possess.

#### IV. RADIATION SAFETY

##### A. GENERAL.

The level of radioactivity at Enewetak Atoll, as reported in the AEC Radiological Survey, is sufficiently low that persons may visit almost every location there without <sup>concern</sup> ~~fear~~ of being exposed to radiation in excess of established radiation protection guides. Cleanup is needed, however, because these guides would be exceeded if persons were to dwell throughout the Atoll. Cleanup itself needs radiation safety precautions because possibilities exist that previously undetected contamination will be uncovered, stockpiling of contaminated debris will enhance local radiation intensity, and cleanup activities will make plutonium more readily available for assimilation before it is contained. The safety precautions will result from a cleanup radiation safety policy which complies with the established guides, as well as makes every reasonable effort to maintain radiation exposure as low as is reasonable achievable taking into account the state of technology and the economics of improvements in relation to benefits to health and safety, and other societal and socioeconomic considerations.

##### B. APPLICABILITY.

1. Cleanup is a responsibility assigned to the Department of Defense and delegated to the Defense Nuclear Agency (DNA). Army engineer personnel will be assigned to perform the physical and radiological cleanup for, under the overall management of, a DNA Joint Task Group. Although support will also come from other military services, federal agencies, and contractors, the Cleanup will be primarily an "Army Job." Accordingly, radiation safety will comply with Army Regulations insofar as is practical.



2. The Army Regulations will apply to all individuals who are at Enewetak Atoll during the period of Cleanup. Personnel not under control of DNA shall comply in all respects with the regulations or be denied access to Enewetak Atoll. The Cleanup Commander may permit variances however, if, in his judgement, an essential task cannot otherwise be accomplished. In such cases, adequate alternate safety procedures will be established.

#### C. CONTROLLED AREAS.

A "controlled area" is a defined area in which the exposure of personnel to ionizing radiation is under the supervision of an individual responsible for radiation protection. Initially, islands listed in Enclosure 2 will be designated as controlled areas. Controls will not be removed until the ERDA representative issues a certification acknowledging that the defined area is rid of contaminated debris and soil as defined in Parts <sup>II</sup> and <sup>III</sup> of this Plan.

#### D. RADIATION PROTECTION STANDARDS.

1. A "radiation worker" is an individual who might be exposed to more than 10 percent of the basic radiation protection standards (See Enclosure 3) as a result of his employment or duties in a controlled area. An "occasionally exposed individual" is one whose work is not normally performed in a controlled area and whose duties do not normally involve exposure to ionizing radiation; however, the individual may have reason to enter a controlled area in the performance of duties. Occasionally exposed individuals will not receive an exposure to ionizing radiation in excess of that allowed for any individual in the population at large.

2. Essentially all of cleanup can be accomplished by personnel categorized as occasionally exposed individuals; accordingly, the majority of the workforce will be treated as such insofar as radiation limits are concerned. If, on the other hand, radiation areas (See IV G.4) should be established, they will be assigned to personnel having the most experience with radiation, and qualifying as radiation workers.

#### E. MEDICAL EXAMINATIONS.

1. Preplacement and termination medical examinations will be given to all cleanup personnel. The examinations will include a review of prior occupational exposure and a description of any unusual exposure resulting from previous occupations, accidents, incidents, or therapeutic procedures, for the purpose of evaluating an individual's acceptability into the cleanup operation. Also, the examinations will include a lung count for any individual who may have worked with plutonium at some previous time.

2. Plutonium represents the greatest radiation hazard facing Cleanup workers. Although plutonium at Enewetak is harmless while it remains outside the body, it could cause deleterious effects if it enters the body. Precautions will be taken to prevent the inhalation or ingestion of plutonium, but a bioassay program will be prescribed to monitor the effectiveness of the precautions.

3. The principal bioassay method will be urine analysis.

Urine samples will be taken on a periodic basis from all workers who at

*Will monitor via nose/purifier,  
If possible, additional sampling will be implemented  
(breath, protective suits)*

any time are in the vicinity of plutonium contamination. Urine samples will be analyzed for plutonium to a sensitivity of at least 0.3 pCi. If positive readings should be obtained, additional bioassays; e.g., fecal analysis or lung counts, will be prescribed.

#### F. TRAINING.

All personnel who may at any time frequent or work in any controlled area will be informed by such means as lectures, briefings, handouts and notices, of:

- (a) Health hazards associated with exposure to radioactive material or radiation,
- (b) precautions or procedures to minimize exposure,
- (c) purposes and functions of protective devices employed,
- (d) decontamination purposes and procedures,
- (e) responsibility of each individual to promptly report any condition which may lead to or cause a violation of radiological safety regulations and procedures or unnecessary exposures,
- (f) radiation exposure reports which will be maintained on each person, and
- (g) management's commitment to keep occupational exposures as low as is reasonably achievable.

Such training will be sufficient to ensure that the workers can correctly answer questions on radiation protection as it relates to their job.

#### G. PERSONNEL DOSIMETRY.

1. The primary dosimetry device will be the film badge, and the Army Photodosimetry Service shall be employed. The film badge contains one or more photographic emulsions and is designed to differentiate between beta particles, gamma rays, and x-rays.
2. A film badge will be worn by all personnel upon entering a controlled area. It will be worn on the front surface below the shoulders, above the hips, and on the outside of clothing, except where contamination of the badge could occur, or in difficult working conditions where the film badge might be lost or damaged. In such cases, the film badge will be worn under protective clothing.
3. The film badge wearer will be responsible for his badge and the contained film and will take care to avoid its exposure to excessive heat, humidity or moisture.
4. A self-reading pocket dosimeter will be worn, in addition to the film badge, at all times when an individual is in a radiation area; i.e., in any area in which there exists radiation at such levels that a major portion of the body could receive in any one hour a dose equivalent in excess of 2 mrem or in any five consecutive days a dose equivalent in excess of 100 mrems. Radiation areas will be identified during the initial radiological reconnaissance of each island. Exposure accumulated by the pocket dosimeters will be documented.

#### H. PROTECTIVE CLOTHING.

1. Plutonium is the only radiological threat of Cleanup which requires a protective-clothing response. As previously noted, Pu in the

ground is not a hazard, but if the ground is disturbed, personnel may come into contact with the Pu and be harmed. Persons operating in the vicinity of the disturbed ground might either inhale resuspended Pu directly, or become externally contaminated and susceptible to subsequent internal contamination of themselves or others. All Cleanup operations which disturb Pu-contaminated soil will thus be performed by personnel adequately protected.

2. The protective clothing prescribed for Pu operations may range from shoe covers and a surgical mask to a full compliment of shoe covers, coveralls, gloves, head covers and facepieces with either filters or air lines. Although it is proper to don adequate protective clothing, there are numerous reasons for not overdressing. For example, full-suiting may be intolerable when worn for extended periods in the warm, humid climate indigeneous to Enewetak. The "protection" provided by the clothes could in fact cause harm by leading to heat injuries. Thus, there is an incentive to wear just what is necessary and no more. The proper and minimum clothing will only be known precisely following an evaluation of on-site monitoring (e.g., air samples and nose swipes) against permissible contamination limits (See Enclosure 3); nevertheless, some initial protective-clothing requirements are described below.

3. With perhaps the exception of Pu suspect areas on Runit, no surface locations at Enewetak Atoll have a sufficiently high Pu concentration that they pose a hazard to persons merely walking on them; i.e., ordinary "foot traffic" is assumed to not create any resuspension prob-

lems and accordingly it requires no protective clothing. Likewise, the vegetation-thinning operations with minimum disturbance to root structures (to permit surveying and soil sampling) will be performed without protective clothing. In the case of Runit, air sampling results reported in the AEC Survey indicate that some caution should always be observed; therefore, the minimal precautions prescribed in the FCDNA Interim Quarantine for Runit Island will continue to be observed on Runit.

4. Personnel who collect surface soil samples from Pu suspect areas conceivably could come into intimate contact with Pu or cause slight local resuspension; consequently, they will wear gloves and surgical masks while performing such tasks.

5. Operations which are likely to stir up dust, such as profile soil sampling in Pu suspect areas, soil excavation, loading and sampling in Pu cleanup areas and contaminated soil disposal, will be performed by personnel fully suited. Further, since any resuspended Pu might be spread downwind from these operations, all personnel in the immediate downwind area will also be fully suited.

6. Transportation of soil from excavation sites to the disposal sites will not require protective clothing as the contaminated soil will be under adequate cover.

## I. DECONTAMINATION

1. In addition to making the Atoll safe for re-inhabitation, an objective of cleanup is to prevent contaminated debris from becoming available on the world market. Since decontamination of contaminated debris (See II.B) is not a viable alternative, all such debris which is collected will be encrypted along with contaminated soil in the burial crater. Cleanup equipment, on the other hand, may possess a residual value which merits decontamination. Thus, all equipment deemed worthy will be decontaminated to permissible levels (See Enclosure 3) before they are returned to use in contamination free sites (on or off the Atoll). If the permissible levels cannot be achieved following thorough decontamination efforts, the equipment will either be transferred safely to users having appropriate licenses or disposed of in the same manner as contaminated debris. All unworthy contaminated equipment will likewise be encrypted.

2. To prevent the spread of contamination by personnel, each person will be thoroughly monitored and decontaminated as necessary prior to exiting from any controlled area.

*It is suggested that an air sampling program  
be initiated for health reasons.*

# SCHEDULE OF INITIAL SOIL SAMPLING FOR ENEWETAK CLEANUP

ISLAND	SURFACE SAMPLES <sup>a</sup> (pCi/g)	PROFILE SAMPLES <sup>a</sup>			PU SUSPECT AREAS	NUMBER OF SAMPLES TO BE TAKEN	CLEANUP VOLUME ESTIMATE (m <sup>3</sup> )
		MAX CONC (pCi/g)	DEPTH MAX CONC (cm)	DEPTH CONC EQUALS 40 (cm)			
Alice	68	170	3.5	9	Samples were from a field approximately 100 m by 100 m near the center of the island. The field will be sampled to a depth of 5 cm at 20 m intervals.	36	1.5X10 <sup>3</sup>
		120	1.0	3			
		100	1.0	3			
Belle	48	200	3.5	14	All but one sample was from a field approximately 120 m by 400 m covering about half of the island. The field will be sampled to a depth of 5 cm at 20 m intervals. The isolated sample (100 pCi/g) was from the lagoon-side beach. Ten samples will be collected from that general area.	157	7.2X10 <sup>3</sup> .1X10 <sup>3</sup>
	70	110	1.0	2			
	43	220	1.0	4			
	46						
	94						
	56						
	100						
Clara	45	65	12.5	16	All but one sample (55 pCi/g) was from a field approximately 140 m by 22 m, toward the northeast end of the island. The field only will be sampled to a depth of 5 cm at 20 m intervals along 4 equally-spaced rows running the length of the field.	32	.5X10 <sup>3</sup>
	55	96	3.5	8			
	88	85	1.0	6			
	44						
Daisy	54	64	12.5	15	All samples were from the southwest side of the island, in two fields approximately 120 m X 180 m and 120 m X 80 m. Both fields will be sampled to a depth of 5 cm at 20 m intervals.	105	3.1X10 <sup>3</sup> 1.4X10 <sup>3</sup>
	51	46	30	none <sup>b</sup>			
	90	190	1.0	4			
	98						
Edna	0	0	0	0	None.	0	0

<sup>a</sup>AEC Report NVO-140 "ENEWETAK RADIOLOGICAL SURVEY" Oct 73, concentrations  $\geq 40$  pCi/g.

<sup>b</sup>Increases to max depth sampled (30 cm).



Irene	280	74	80	84	Samples were from an annular field about 600 m long surrounding the Seminole crater and extending landward about 80 m and from a field approximately 100 m X 350 m on the southern coast. The annulus gave a single very-high value (670 pCi/g) sample from the northern end. An area approximately 60 m X 100 m, enclosing this sample location, will be sampled to a depth of 30 cm in 10 cm increments, at 20 m intervals (384 samples). The remainder of the annulus will be sampled to a depth of 5 cm at 40 m intervals (48 samples). The rectangular field will be sampled every 10 cm to a depth of 40 cm at 50 m intervals (96 samples).	528	4.8X10 <sup>3</sup> 6.0X10 <sup>3</sup> 14.0X10 <sup>3</sup>
	95	100	30	57			
	210	170	30	none <sup>c</sup>			
		670	12.5	none <sup>d</sup>			
		170	30	43			
Janet	41	65	1.0	2.0	Samples were from two fields: 720 m X 220 m and 180 m X 540 m. A qualifying sample outside of these fields was from a 12-acre site which ERDA is using for experimental purposes and has claimed to have no significant Pu contamination. Thus, that sample will be ignored. Samples will be collected from the fields to a depth of 5 cm and at 20 m intervals.	686	2.4X10 <sup>3</sup> 1.5X10 <sup>3</sup>
	45	55	2.5	9.0			
	170	110	3.5	8.0			
	41						
	51						
	46						
	67						
	48						
	52						
	120						
	66						
	40						
	57						
Kate	50	62	1.0	2.0	Samples were from opposite sides of the island and suggest that no significant hot spots are present. However, as there is a paucity of data for locations closely surrounding the two sampled-points, ten 5 cm deep samples will be collected from the general area of each.	20	.1X10 <sup>3</sup> .1X10 <sup>3</sup>

<sup>c</sup>Essentially 110 to max depth sampled (60 cm).

<sup>d</sup>115 at max depth sampled (37 cm).

Lucy	0	48	1.0	1.5	Samples were from opposite sides of the island and suggest that no significant hot spots are present. Since all analyses are nominally the same as the lower Guideline, the island will be considered to have no Pu suspect area; no samples will be taken.	0	0
Percy	0	43	7.5	8.0	The single analysis which exceeds 40 pCi/g is sufficiently close to that limit that no additional samples will be taken. The island will be considered to have no Pu suspect area.	0	0
Mary	0	55 40	3.5 3.5	5.0 3.5	Both analyses are close to the 40 pCi/g Guideline and in each case the samples were from locations within 20 m of locations which gave Pu concentrations less than 40 pCi/g. The island will be considered to have no Pu suspect area; no samples will be taken.		
Nancy	0	42	7.5	8.0	The sole sample exceeds 40 pCi/g by a small margin, and it was from a location near to ones which gave Pu concentration less than 40 pCi/g. The island will be considered to have no Pu suspect area; no samples will be taken.	0	0
Olive	0	85 85 47	1.0 1.0 3.5	2.0 2.5 4.0	Samples were from a field approximately 120 m X 180 m toward the northern end of the island. The field will be sampled to a depth of 5 cm at 20 m intervals.	70	1.4x10 <sup>3</sup>

Pearl	170 530 63 55 83 85 81 50 83 89 100 170	410	1.0	5.0	All but one sample was from a field running north-to-south, approximately 160 m X 340 m. The field will be sampled to a depth of 5 cm at 20 m intervals. The isolated sample (170 pCi/g) was taken from the lagoon-side beach toward the western end of the island. Ten samples will be collected from that general area.	172	.8X10 <sup>3</sup> .1X10 <sup>3</sup>
Ruby	0	0	0	0	None.	0	0
Sally	44 130	40 64 68	130 1.0 1.0	130 2.0 2.0	Samples reading 44 and 64 pCi/g were from the islet (often called "Sally's Child") which is approximately 60 m X 220 m. Ten additional samples will be taken from the general area toward the center of the islet. The remaining samples were from locations spaced along the lagoon-side beach. Ten samples will be taken from the area toward the western trip which gave the 130 pCi/g value.	20	.1X10 <sup>3</sup> .1X10 <sup>3</sup>
Tilda	0	0	0	0	None.	0	0
Ursula	0	0	0	0	None.	0	0
Vera	0	0	0	0	None.	0	0
Wilma	0	0	0	0	None.	0	0
Yvonne A		75 180 54 150	5 15 55 25	14 19 & 108 58 44	Samples were from a field approximately 80 m X 300 m toward the north-western periphery of the island. The field will be sampled to a depth of 60 cm at 10 cm increments and at 50 m intervals (84 samples).	84	14.4X10 <sup>3</sup>

Yvonne	150	800	95	112
B		520	15	23
		820	70	140
		480	35	55
		75	75	77
		110	35	48
		95	25	30
		100	15	20
		450	5	32
		220	5	8
		730	5	9
		310	5	32
		320	5	9
		370	5	23
		62	5	6
		52	2.5	4
		52	5	6
		300	5	30
		62	5	7
		160	5	11
		150	or 15 ?	?

Samples were from a field centered in the island (portion) approximately 140 m (from lagoon to ocean) by 520 m. Although many high readings are near the air-ground interface, concentrations at depths up to 140 cm are significant. Except for four locations, clustered near the "right-side" of the field, profiles decrease to less than 40 pCi/g within about the top 35 cm. Samples will be taken to a depth of 40 cm at 10 cm increments and at 20 m intervals (864 samples). At the high-value area (140 m X 200 m), samples will be taken to additional depths of 100 cm (880 additional samples).

1744	29.2X10 <sup>3</sup>
	28.0X10 <sup>3</sup>

Yvonne	50	62	14	15
C	40	290	75	93

Samples were from widely separated locations, each with adjacent analyses that did not exceed 40 pCi/g, which suggests that no extended hot spots are present. The one high reading, from the middle, northern side of the runway, will be investigated. Samples at 10 cm increments to depths of 100 cm will be collected from 10 locations in an area approximately 50 m X 80 m encompassing the high value.

100	4.0X10 <sup>3</sup>
-----	---------------------

TOTALS	3754	120.8X10 <sup>3</sup>
--------	------	-----------------------

ENEMYTAK ISLANDS TO BE SEARCHED  
FOR CONTAMINATED DEBRIS

<u>ISLAND</u>	<u>TOTAL AREA*</u> (acres)	<u>PU SUSPECT AREA</u> (acres)	<u>OVERGROWN AREA**</u> (acres)
Alice	22	3	15
Belle	30	12	12
Clara	7	1	5
Daisy	21	8	2
Edna	10	-0-	-0-
Irene	45	20	6
<del>Janet***</del>	291	63	100
Kate	16	-0-	14
Lucy	20	-0-	18
Percy	2	-0-	-0-
Mary	12	-0-	9
Nancy	11	-0-	11
Olive	41	5	36
Pearl	54	13	36
Ruby	4	-0-	-0-
Sally	99	-0-	50
Tilda	52	-0-	45
Ursula	40	-0-	36
Vera	38	-0-	38
Wilma	-0-	-0-	12
Yvonne	<u>94</u> 909	<u>25</u> 150	<u>35</u> 480

\*from TABLE 5-16, EIS

\*\*Pu suspect areas excluded

\*\*\*Approximately 12 acres under experimental cultivation by ERDA will be excluded from Cleanup

Encl 2

1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1

RADIATION PROTECTION STANDARDS FOR CLEANUP

A. Control of Occupational Exposure to Ionizing Radiation (AR 40-14)

(1) The accumulated dose equivalent of radiation of the whole-body, head and trunk, active blood-forming organs, gonads, or lens of the eye will not exceed--

(a) 1.25 rems in any calendar quarter,

nor

(b) 5 rems in any 1 calendar year.

(2) The accumulated dose equivalent of radiation to the skin of the whole-body (other than hands and forearms), cornea of the eye, and bone will not exceed--

(a) 7.50 rems in any calendar quarter,

nor

(b) 30 rems in any 1 calendar year.

(3) The accumulated dose equivalent of radiation to the hands and wrists or the feet and ankles will not exceed--

(a) 18.75 rems in any calendar quarter,

nor

(b) 75 rems in any 1 calendar year.

(4) The accumulated dose equivalent of radiation to the forearms will not exceed--

(a) 10 rems in any calendar quarters,

nor

(b) 30 rems in any 1 calendar year.



(5) The accumulated dose equivalent of radiation to the thyroid, other organs, tissues, and organ system will not exceed--

(a) 5 rems in any calendar quarter, nor

(b) 15 rems in any 1 calendar year.

(6) Individual(s) under 18 years of age, females known to be pregnant, and occasionally exposed individual(s) will not be exposed to a whole-body dose equivalent of more than--

(a) 2 millirems in any 1 hour, nor

(b) 100 millirems in any 7 consecutive days nor

(c) 500 millirems in any 1 calendar year,

(d) nor more than 10 percent of the values in (2), (3),

(4) and (5), above, for other areas of the body.

(7) Individuals over 18 years of age, but who have not yet reached their 19th birthday, may be occupationally exposed to ionizing radiation provided that they do not exceed 1.25 rems dose equivalent to the whole-body in any calendar quarter, nor 3 rems in the 12 consecutive months prior to their 19th birthday.

#### B. Permissible Contamination Levels

(1) Soil:

Less than 40 pCi (Pu)/g (AEC Task Group)

(2) Debris, vehicles and other equipment released after any cleanup:

(a) Transuranic alpha emitters--less than 20 dpm/100 cm<sup>2</sup>

(NRC Regulatory Guide 1.86)

(b) Beta/Gamma emitters--less than 0.1 mrad/hr at 1 cm

(ERDA Property Management Instruction 109-45 and


NRC Regulatory Guide 1.86)

(3) Personnel:

No removable contamination (AR 700-64)

(4) Air:

Less than 4.4 dpm (Pu-239)/m<sup>3</sup> (10 CFR 20)







HOLMES & NAVER, INC.  
ENGINEERS - CONSTRUCTORS  
PACIFIC TEST DIVISION

TIME: MARCH 11, 1941  
MEDICAL FACULTY  
PLANNING COMMITTEE

NOTE: THIS ESTIMATE DOES NOT INCLUDE COST FOR LCU, MODIFICATION,  
TRANSPORTATION COST OR PART HANDLING OF LCU TO ANY  
THAT MAY BE REQUIRED

MARSHALL ISLANDS MEDICAL FACILITY

AFH

SUB ACTY. NO.	DESCRIPTION	QUANTY	UNIT	DIRECT LABOR		MATERIAL		EQUIPMENT		TOTAL
				UNIT	AMOUNT	UNIT	AMOUNT	UNIT	AMOUNT	
	THIS PLANNING ESTIMATE IS IN ACCORDANCE WITH BROOKHAVEN NATIONAL LABORATORY LETTER DATED 7/25/73 W/ ATTACHED SKETCHES									
	MEDICAL TRAILER									
150	CARPENTRY									
	(PARTITIONS)									
LABORATORY	8' W X 8' H ± 64 SF									
	MISC. MAT'L					LS	192			192
	CARPENTER	24	MH.	10 <sup>50</sup>	252					252
	LABORER	8	MH.	10 <sup>50</sup>	84					84
WARD	SHED W/ 1 9' W X 8' H ± 32 SF									
	MISC. MAT'L					LS	160			160
	CARPENTER	16	MH.	10 <sup>50</sup>	168					168
	LABORER	4	MH.	10 <sup>50</sup>	42					42
WARD	6' W X 8' H ± 28 DOOR TRIM & HARDWARE									
	MISC. MAT'L ± 48 SF					LS	144			144
	DOOR W/ TRIM & HARDWARE					LS	75			75
	CARPENTER	24	MH.	10 <sup>50</sup>	252					252
	LABORER	8	MH.	10 <sup>50</sup>	84					84
TOILET	6' W X 8' H ± 28 DOOR, TRIM & HARDWARE									
	MISC. MAT'L					LS	144			144
	DOOR W/ TRIM & HARDWARE					LS	75			75
	CARPENTER	24	MH.	10 <sup>50</sup>	252					252
	LABORER	8	MH.	10 <sup>50</sup>	84					84
	LAB. BENCH 6' L X 3' H X 1 1/2' W					GFE				
	MISC. MAT'L						10			10
	TOP						15			15
	MISC. HARDWARE						10			10
	CARPENTER	8	MH.	10 <sup>50</sup>	84					84
	LABORER	4	MH.	10 <sup>50</sup>	42					42
	METH. TYPE CABINETS OVER WORK BENCH 8' ± 36" WIDE					GFE				
	CARPENTER	6	MH.	10 <sup>50</sup>	63					63
	SUB-TOTAL CARRIED FORWARD									
	154				1407		825			2232

# DETAIL ESTIMATE

FORM 407-3

OPERATION

ITEM NO.

SHEET NO. 4 OF 13

MARSHALL ISLANDS MEDICAL FACILITY

JOB

EST. NO. 90575

EST. BY

AFA

DATE 8/6/75

SUB ACCT. NO.	DESCRIPTION	QUANTITY	UNIT	DIRECT LABOR		MATERIAL		EQUIPMENT		TOTAL
				UNIT	AMOUNT	UNIT	AMOUNT	UNIT	AMOUNT	
150	CARPENTRY									
	SUB-TOTAL BROUGHT FORWARD	134			1007		825			2232
	DRYING TABLE 36 L X 3 H X 2 W						GFE			
	MISC. WOOD					45	10			10
	TOP ± 6" ±					45	10			10
	MISC. HARDWARE					15	5			5
	CARPENTER	8	MH. 10 <sup>00</sup>		84					84
	LABORER	4	MH. 10 <sup>00</sup>		42					42
	MARINE CABINETS ± 4 LONG X 12 WIDE X 12 HIGH PANELS						GFE			
	CARPENTER	6	MH. 10 <sup>00</sup>		63					63
	LABORER	2	MH. 10 <sup>00</sup>		21					21
	DRESSER FIELD W/ MARINE CABINET						GFE			
	CARPENTER	6	MH. 10 <sup>00</sup>		63					63
	LABORER	2	MH. 10 <sup>00</sup>		21					21
	WOOD STAIRS & PLINTHS ALLOW FOR (1) ONE ONLY. MISC. WOOD & HARDWARE						150			150
	CARPENTER	16	MH. 10 <sup>00</sup>		168					168
	LABORER	4	MH. 10 <sup>00</sup>		42					42
	MISC. CARPENTRY THAT WILL BE NEEDED TO ALTER TRAILER	52	MH. 10 <sup>00</sup>		520	1.5	100			436
	MISC. CARPENTRY TO DO WHAT'S NEEDED TO SHIP TRAILER TO OUTER ISLAND	24	MH. 10 <sup>00</sup>		240	1.5	25			271
	PACKING & CRATING AS MAY BE REQUIRED	80	MH. 10 <sup>00</sup>		840	1.5	250			1090
	MISC. FIELD WORK	32	MH. 10 <sup>00</sup>		336		100			436
	MISC. EQUIPMENT W/ WORK MATERIAL HANDLED 15%	16	MH. 10 <sup>00</sup>		163			7 <sup>00</sup>	120	283
	TOTAL S/A	366			3843		1696		120	5659

## DETAIL ESTIMATE

OPERATION

ITEM NO.

SHEET NO. 5 OF 13

MARSHALL ISLANDS MEDICAL FACILITY

JOB

EST. NO. 92575

EST. BY AFA

DATE 8/6/73

SUB ACCT. NO.	DESCRIPTION	QUANTITY	UNIT	DIRECT LABOR		MATERIAL		EQUIPMENT		TOTAL
				UNIT	AMOUNT	UNIT	AMOUNT	UNIT	AMOUNT	
410	PAINT WORK									
	CUT OPENING @ END OF TRAILER FOR NEW DOOR.									
	MISC PAINT					1.5	50			50
	1 DOOR W/ HANDSOME E. TRIM					1.5	100			100
	CHALK PASTER	24	MH 10 <sup>10</sup>		252					252
	LABORER	6	MH 10 <sup>10</sup>		63					63
	MAT'L HANDLING 15%						23			23
	Total S/A	30			315		173			488
460	PLUMBING									
	(SINK, W/ HOT WATER TANK)									
	METAL SINK	8	MH 10 <sup>10</sup>		84	1.5	50			134
	Faucet & SPRAYER	8	MH 10 <sup>10</sup>		84	1.5	50			134
	BASE CUPINET (WOOD OR METAL)	8	MH 10 <sup>10</sup>		84	1.5	50			134
	SPRAYER COMPLETE	16	MH 10 <sup>10</sup>		168	1.5	150			318
	WATER CLOSET, CERAMIC									
	TOILET COMPLETE w/ all									
	CONNECTIONS	24	MH 10 <sup>10</sup>		252	1.5	250			502
	HOT WATER HEATER	8	MH 10 <sup>10</sup>		84	1.5	75			159
	MISC PIPING & etc.	40	MH 10 <sup>10</sup>		420	1.5	250			670
	REFRIGERATOR (21 CU FT)	4	MH 10 <sup>10</sup>		42	1.5	450			472
	DEEP FREEZER (21 CU FT)	4	MH 10 <sup>10</sup>		42	1.5	400			442
	WATER PUMP & PIPING	24	MH 10 <sup>10</sup>		252	1.5	250			602
	WATER TANK (1000 gals)	24	MH 10 <sup>10</sup>		252		1000			1252
	FIELD CONNECTIONS	40	MH 10 <sup>10</sup>		420					420
	MISC EQUIPMENT w/ CORR.	16	MH 10 <sup>10</sup>		168			7 <sup>00</sup>	120	288
	MAT'L HANDLING 15%						461			461
	Total S/A	224			2352		2536		120	6008

# DETAIL ESTIMATE

OPERATION

ITEM

SHEET NO. 6 OF 12

MARSHALL ISLANDS MEDICAL FACILITY

JOB

EST. NO. 90575

EST. BY

RAFA

DATE 8/6/73

SUB AMT. NO.	DESCRIPTION	QUANTITY	UNIT	DIRECT LABOR		MATERIAL		EQUIPMENT		TOTAL
				UNIT	AMOUNT	UNIT	AMOUNT	UNIT	AMOUNT	
470	AIR CONDITIONING									
	MAKE OPENING TO RECEIVE A/C UNIT									
	2-1 TEN UNITS (+13000 BTL)	32	MH. 10 <sup>00</sup>		336		600			936
	MAT'L HANDLING 15%						90			90
	MISC FIELD WORK	16	MH. 10 <sup>00</sup>		168					168
	TOTAL 5/A	48			504		690			1194
600	ELECTRICAL									
	INSTALL DISTRIBUTION PANEL, NEW LIGHT FIXTURES, ELECTRIC OUTLETS FOR WORK BENCHES, REFRIGERATOR, X-RAY MACHINE Etc.	120	MH. 10 <sup>00</sup>		1260					1260
	MISC MAT'L & etc.					1.5	1200			1800
	MISC FIELD WORK	40	MH. 10 <sup>00</sup>		420					420
	MISC EQUIPMENT w/ORK	16	MH. 10 <sup>00</sup>		168					168
	MAT'L HANDLING 15%						180		120	300
	TOTAL 5/A	176			1848		1380		120	3348
620	SPECIAL EQUIP									
	REPAIRS & 3' 3150 + 15%						(3523)			
	TRANSPORTATION						(175)			
	SHIPPING TO HONO						(1173)			
	PORT HANDLING						(476)			
	ESTIMATED COST						5372			5372
	PREPARE FOR SHIPPING	40	MH. 10 <sup>00</sup>		420					420
	HANDLING & TRANSPORT	16	MH. 10 <sup>00</sup>		168					168
	MISC FIELD WORK	24	MH. 10 <sup>00</sup>		252					252
	MISC EQUIPMENT	16	MH. 10 <sup>00</sup>		168					168
	TOTAL 1/A	96			1008		72		220	1600

## DETAIL ESTIMATE

OPERATION

ITEM NO.

SHEET NO. 7 OF 13

MARSHALL ISLANDS MEDICAL FACILITY

JOB

EST. NO. 90575

EST. BY

AFA

DATE

8/6/73

SUB ACCT. NO.	DESCRIPTION	QUANTITY	UNIT	DIRECT LABOR		MATERIAL		EQUIPMENT		TOTAL
				UNIT	AMOUNT	UNIT	AMOUNT	UNIT	AMOUNT	
630	PAINTING									
	PAINT NEW PARTITION, DOORS & METAL	56	MH 10 <sup>3</sup>		533	15	65			653
	MAT'L HANDLING 15%						10			10
	TOTAL S/A	56			533		75			663
640										
700	ELECTRICAL UTILITIES SYSTEM									
	50 KW GENERATOR w/ INSTRUMENT PANEL 6420 ± 5% = 6741 TRANSPORTATION 300						7041			7041
	PREPARE GENERATOR FOR SHIPPING & WARE FRIDGE FOR PANEL BOARD	43	MH 10 <sup>3</sup>		504	15	225			729
	TRUCK w/ OPR	8	MH 10 <sup>3</sup>		84			7 <sup>30</sup>	60	144
	MISC FIELD WORK	16	MH 10 <sup>3</sup>		168					168
	MAT'L HANDLING 15%						1056			1056
	TOTAL S/A	72			756		8322		60	9123
712	FUEL UTILITIES SYSTEM									
	FUEL TANK ± 400 gal					15	400			400
	WOOD SKID FOR TANK	24	MH 10 <sup>3</sup>		250	15	100			352
	MISC TANKS & FUEL TANK TO GENERATOR	16	MH 10 <sup>3</sup>		168	15	150			318
	MISC FIELD WORK	16	MH 10 <sup>3</sup>		168					168
	MISC EQUIPMENT OPR	8	MH 10 <sup>3</sup>		84			7 <sup>30</sup>	60	144
	MAT'L HANDLING 15%						98			98
	TOTAL S/A	64			672		743		60	1430



## DETAIL ESTIMATE

OPERATION

ITEM NO.

SHEET NO. 8 OF 13

MARSHALL ISLANDS MEDICAL FACILITY

JOB

EST. NO. 90573

EST. BY AFA

DATE 8/6/53

SUB ACCT. NO.	DESCRIPTION	QUANTITY	UNIT	DIRECT LABOR		MATERIAL		EQUIPMENT		TOTAL
				UNIT	AMOUNT	UNIT	AMOUNT	UNIT	AMOUNT	
640	FURNISHINGS									
	XRAY MACHINE ACCESSORIES						GFE			
	FLUORE PHOTOMETER						GFE			
	SURGICAL CABINET						GFE			
	EXAMINATION TABLE & CHAIRS						GFE			
	PORTABLE SURGICAL LIGHT						GFE			
	SURGICAL TRAY, MOBILE						GFE			
	STERILIZER						GFE			
	DENTAL CHAIR						GFE			
	(ON HAND) MICROSCOPES, REG.						GFE			
	FASTEN DOWN THE ABOVE EQUIPMENT AS LOCATED ON SKETCH.									
	CARPENTER	96	MH. 10 <sup>30</sup>		1008					1008
	LABORER	48	MH. 10 <sup>30</sup>		504					504
	FORK LIFT W/OPR	12	MH. 10 <sup>30</sup>		126					126
	MISC. MTL & HARDWARE					15	250			250
	TRUCK W/OPR	8	MH. 10 <sup>30</sup>		84			7 <sup>00</sup>	60	144
	MISC FIELD WORK	40	MH. 10 <sup>30</sup>		400					400
	MTL & HANDLING 15%						38			38
	TOTAL S/A	204			2142		288		60	2490
780	SUPERVISION	104	MH. 10 <sup>30</sup>		1096					1096
	MISC. FIELD WORK	40	MH. 10 <sup>30</sup>		400					400
	TOTAL S/A	144			1512					1512



# DETAIL ESTIMATE

OPERATION

ITEM NO.

SHEET NO. 9 OF 13

MARSHALL ISLANDS MEDICAL FACILITY

JOB

EST. NO. 90575

EST. BY AFA

DATE 8/7/73

SUB ACCT. NO.	DESCRIPTION	QUANTITY	UNIT	DIRECT LABOR		MATERIAL		EQUIPMENT		TOTAL
				UNIT	AMOUNT	UNIT	AMOUNT	UNIT	AMOUNT	
	WHOLE BODY COUNTER TRAILER (25'x8')									
150	CARPENTRY									
DRFSS & RM.	PARTITIONS, BENCHES ETC 110'x8'4" ± 80 SF					1.5	240			240
BENCH	± 9'4" ± 30 SF					1.5	20			20
	MISC. HARDWARE ETC					1.5	10			10
	CARPENTER	24	HH 10 <sup>50</sup>		252					252
	LABORER	8	HH 10 <sup>50</sup>		84					84
WANTING RM.	± 5'x8' ± 64 SF					1.5	192			192
BENCH	± 10'4" ± 40 SF					1.5	30			30
	DOOR W/ KINIE HARDWARE					1.5	75			75
	MISC HARDWARE ETC.					1.5	15			15
	CARPENTER	32	HH 10 <sup>50</sup>		336					336
	LABORER	8	HH 10 <sup>50</sup>		84					84
DOORS	PROVIDE DOORS TO TRAILER AS PER SKETCH. CUT OPENINGS TO RECEIVE 3 DOORS W/ HARDWARE									
	MISC. HMTL. HARDWARE					1.5	225			225
	CARPENTERS	64	HH 10 <sup>50</sup>		672					672
	LABORER	16	HH 10 <sup>50</sup>		168					168
A/C.	PREPARE OPENINGS TO RECEIVE A/C. UNITS									
	MISC. HMTL.					1.5	30			30
	CARPENTER	24	HH 10 <sup>50</sup>		252					252
SUB-TOTAL CARRIED FORWARD		176			1848		837			2685

## DETAIL ESTIMATE

OPERATION

ITEM NO.

SHEET NO. 10 OF 13

MARSHALL ISLANDS MEDICAL FACILITY

JOB

EST. NO. 90575

EST. BY RFR

DATE 8/1/73

SUB ACCT. NO.	DESCRIPTION	QUANTITY	UNIT	DIRECT LABOR		MATERIAL		EQUIPMENT		TOTAL
				DAILY	AMOUNT	UNIT	AMOUNT	UNIT	AMOUNT	
	WHOLE BODY COUNTER TRAILER (CONT.)									
150	CARPENTRY									
	SUB-TOTAL BROUGHT FORWARD	176	MH		1848		837			2685
	SHIELD COUNTER									
	ST. 2 1/2' X 4' X 14" = 856"	16	MH 10 <sup>50</sup>		168	L.S.	260			428
	LEAD BRICKS. ± 600 EA.	48	MH 10 <sup>50</sup>		504	GFE				504
	3/4" PLYWOOD TO FACE BOTH SIDES OF LEAD BRICKS AS PER SKETCH & COUNTER									
	B.P.E. 3/4" X 4 X 8	256 <sup>50</sup>	40	MH 10 <sup>50</sup>	420	L.S.	154			574
	B.P.E. 1" X 4 X 8	64 <sup>50</sup>	8	MH 10 <sup>50</sup>	84	L.S.	65			149
	MISC. LUMBER & MAT'L.	16	MH 10 <sup>50</sup>		168	L.S.	125			293
	WORK BENCH									
	1 P.E. 1" X 4 X 8 PLYWOOD									
	MISC LUMBER FOR BENCH									
	& SHELF W/ WOOD WHEELS					L.S.	100			100
	CARPENTER	24	MH 10 <sup>50</sup>		252					252
	LABORER	4	MH 10 <sup>50</sup>		48					48
	CRYSTAL ASSEMBLY						GFE			
	WOOD STAIRS & PLATFORMS									
	ALLOW FOR (2) TIER									
	MISC MAT'L & HARDWARE									
	CARPENTRY	48	MH 10 <sup>50</sup>		504					504
	LABORER	8	MH 10 <sup>50</sup>		84					84
	PACKING & CRATING									
	AS MAY BE REQUIRED	40	MH 10 <sup>50</sup>		420	L.S.	150			570
	MISC CARPENTRY TO DO WHAT'S NEEDED TO SHIP TRAILER TO OUTER ISLAND	24	MH 10 <sup>50</sup>		252	L.S.	25			277
	MISC FIELD WORK	40	MH 10 <sup>50</sup>		420	L.S.	100			520
	TRUCK W/ OPR	16	MH 10 <sup>50</sup>		168			7 <sup>50</sup>	120	288
	MAT'L HANDLING 15%						272			272
	TOTAL S/A	508			5334		2088		120	7542

ITEM NO.

SHEET NO.

110513

MARSHALL ISLANDS MEDICAL FACILITY

JOB

EST. NO.

90575

EST. BY

ATA

DATE

8/7/73

QTY	DESCRIPTION	QUANTITY	UNIT	UNIT LABOR	MATERIAL	EQUIPMENT	TOTAL	
				CHG	AMOUNT	UNIT	AMOUNT	
	WHOLE BODY COUNTER TRAILER (CONT)							
410	MILWAUKEE							
	(SEE DOGRIN SH 150)							
440	PLANING							
	THOUGHT COMPLETE	16	MH 10 <sup>50</sup>	168	15	150		318
	WATER TANKS & PIPING	24	MH 10 <sup>50</sup>	252	15	350		602
	WATER TANK (4,500 GAL)	16	MH 10 <sup>50</sup>	168	15	200		663
	MISC PIPING ETC	16	MH 10 <sup>50</sup>	168	1.5	125		293
	FIELD CONNECTIONS	16	MH 10 <sup>50</sup>	168		25		193
	TRUCK W/FORM	8	MH 10 <sup>50</sup>	84		750	60	144
	MAT'L HANDLING 15%				173			173
		96		1008	1323	60		2391
470	AIR CONDITIONING							
	2 1/2 TON A/C UNITS	8	MH 10 <sup>50</sup>	84		400		484
	(SEE SH 150 A/C)							
	MISC FIELDWORK	16	MH 10 <sup>50</sup>	168				168
	MAT'L HANDLING 15%				60			60
	TOTAL S/A	24		252	460			712

## OPERATION

ITEM NO.

SHEET NO. 13 OF 15

Marshall Islands Medical Facility

JOA

EST. NO. *90-734*

EST. BY *HFA*

DATE *8/7/77*

SUB ACCT. NO.	DESCRIPTION	QUANTITY	UNIT	DIRECT LABOR		MATERIAL		EQUIPMENT		TOTAL
				UNIT	AMOUNT	UNIT	AMOUNT	UNIT	AMOUNT	
	WHOLE BODY COUNTER TRAINER (CONT)									
630	PAINTING									
	PAINT NEW PARTITIONS, DECKS, BENCHES & METAL	56	MM 10 <sup>50</sup>	588		15	65			653
	MAT'L HANDLING 15%						10			10
	TOTAL S/A	56		588		75				663
640	FURNISHING									
	CRYSTAL ASSEMBLY					GFE				
700	ELECTRICAL UTILITIES									
	MAKE UP POWER CONNECTION FROM TRAILER TO GENERATOR.	16	MM 10 <sup>50</sup>	168		15	150			318
	MISC. FIELD WORK	8	MM 10 <sup>50</sup>	84		15	20			104
	TOTAL S/A	24		252		170				422
780	SUPERVISION									
	MISC. FIELD WORK	16	MM 10 <sup>50</sup>	168						168
	TOTAL S/A	88		904						924

## DETAIL ESTIMATE

OPERATION

ITEM NO.

SHEET NO. 12 OF 13

MARSHALL ISLANDS MEDICAL FACILITY

JOB

EST. NO. 90575

EST. BY

AFA

DATE 8/17/73

SUB ACCT. NO.	DESCRIPTION	QUANTITY	UNIT	DIRECT LABOR		MATERIAL		EQUIPMENT		TOTAL
				UNIT	AMOUNT	UNIT	AMOUNT	UNIT	AMOUNT	
	WHOLE BODY COUNTER TRAILER (CONT)									
600	ELECTRICAL									
	INSTALL DISTRIBUTION PANEL, NEW LIGHT FIXTURES, ELECTRIC OUTLETS FOR WORK BENCH & WATER PUMP	64	MH 10 <sup>50</sup>	672	1.5	550				1222
	MISC. FIELD WORK	24	MH 10 <sup>50</sup>	252						252
	TRUCK W/OVR									
	MISC EQUIPMENT W/OVR	8	MH 10 <sup>50</sup>	84				7 <sup>50</sup>	60	144
	MAT'L HANDLING 15%					83				83
	TOTAL S/A	96		1008		633		60		1701
620	SPECIAL EQUIPMENT									
	TUMEX 125' X 8' 2850 + 15%					( 3278 )				
	TRANSPORTATION					( 175 )				
	SHIPPING					( 950 )				
	PORT HANDLING					( 400 )				
	ESTIMATED COST					4803				4803
	PREPARE FOR SHIPPING	40	MH 10 <sup>50</sup>	420						420
	HANDLING & TRANSPORT	16	MH 10 <sup>50</sup>	168				100		268
	MISC FIELD WORK	24	MH 10 <sup>50</sup>	252						252
	MISC EQUIPMENT W/OVR	16	MH 10 <sup>50</sup>	168				7 <sup>50</sup>	120	288
	TOTAL S/A	96		1008		4803		220		6031