

# **TSA-RE Dry Pendant Sprinklers Replacement at the AMWTP ...a Success Story**

**David K. Young, P.E.**

**DOE Fire Safety Workshop**

**April 2008**



**HUGHES ASSOCIATES, INC.**

**FIRE SCIENCE & ENGINEERING**

# Safety Share

- How **NOT** to dispose of a can of WD40 or other aerosol.



# Transuranic Storage Area – Retrieval Enclosure (TSA-RE)



Transuranic Storage Area –  
Retrieval Enclosure (TSA-RE)



# Background

- Original dry pendant installation
  - ◆ Originally installed as pre-action (1996) and consisted of 8 independent systems using Grinnell Model F-960 dry-pendent sprinkler heads
  - ◆ Issues with linear beam detectors (alignment)
  - ◆ Converted to dry pipe in late 1990's



# Background, Cont.




# Equivalency Evaluation

- Dry system did not meet NFPA 13 criteria (system volume too large, time for water delivery too long)
  - ◆ Equivalency written and approved by DOE-ID



# Equivalency Evaluation, Cont.



- In early 2002, an equivalency was prepared for the system size and water delivery time delay issues
  - ◆ Equivalency based on over design of the system for the commodity classification
  - ◆ Class IV commodity sprinkler design for a Class III commodity
  - ◆ DOE-ID approval received in August of 2002



# Discovery of the Problem

- 10-year testing per NFPA 25, Section 5.3.1.1.1.5, was due in 2006
- Scheduled with initial sample of 35 (representing all 8 sprinkler systems) removed by support subcontractor and sent to UL for testing
  - ◆ 21 were actually tested as the remainder were damaged during removal
  - ◆ The sample tested represented the entirety of the sprinklers in the TSA-RE
- Of the 21 tested, 1 failed
  - ◆ NFPA 25, Section 5.3.1.3 states, “*Where one sprinkler within a representative sample fails to meet the test requirement, all sprinklers represented by that sample shall be replaced.*”



## Discovery of the Problem, Cont.

- The issue with replacement is that each of the 8 sprinkler systems have roughly 430 sprinklers, for a total of approximately 3440 sprinklers



# Discovery of the Problem, Cont.



Problem now?



# Discovery of the Problem, Cont.



Fiberglass reinforced plywood boxes

Tarp and plywood sheet material

How about now?



# New Equivalency Investigation

- FPEs and management agreed it was prudent to test additional sprinklers
  - ◆ Was an equivalency possible based on
    - 25-psi operating pressure?
    - Robust water supply?
    - Equivalency on top of an equivalency?
  - ◆ 10 sprinklers from 8 systems removed and tested
- 80 sprinklers sent to UL for testing (plunge test)
  - ◆ 75 actually tested (remainder damaged during removal)
  - ◆ 5 failures (of total population 6 of 96 failed: 6%)
  - ◆ Failures ranged from activation at 36 psi up to did not operate at 100 psi
- Based on a 6% failure rate and the condition of some of the removed sprinklers, absolutely no technical basis to pursue equivalency





10/25/2007



# Code Compliant Options

- Antifreeze system
- Wet system
- Dry system
- Sprinkler replacement



# Selection Process

## ■ Glycol

### ◆ Not selected

- Estimated cost \$1.8M
- Expansion tank size
- Additional cost due to ongoing maintenance

## ■ Wet

### ◆ Not selected

- Estimated cost \$2.2M
- Volume of heated space ~ 13 M ft<sup>3</sup> (hard to heat)
- Addition of insulation
- Rework of each of the fire risers






# Selection Process, Cont.


- Upright dry
  - ◆ Not selected
    - Estimated cost \$1.5M
    - Extensive pipe rework
- Direct Replacement
  - ◆ Selected
    - Estimated cost \$700K
    - Cost was a significant consideration
    - A non O-ring design might be more reliable



# Selection Process, Cont.



Grinnell Model F-960,  
Standard Response



Victaulic Model V3605,  
Standard Response



# Selection Process, Cont.




# Sprinkler Replacement and Installation

- RFP sent to solicit bids for work
  - ◆ Two attended pre-bid walkthrough
  - ◆ One submitted a bid
- Method of replacement
  - ◆ From above with temporary “scaffolding” and tie-offs
  - ◆ 100% fall protection
- Replacement work began August 27, 2007



# Sprinkler Replacement and Installation, Cont.



# Fall Protection and Rescue Devices



Horizontal Lifeline System



First-man Up Pole System



Rescue Positioning Device



# Sprinkler Replacement and Installation, Cont.

## ■ Challenges

- ◆ Coordination with operations
  - FHA required no operations take place while sprinkler system was out of service
- ◆ Physically reaching all 3440 sprinklers
- ◆ Thermally hot/cold environment



# Installation

- Project management and support
  - ◆ Coordination of contract documents
  - ◆ Recommendations/suggestions regarding fall protection equipment
  - ◆ On site during project to ensure work running smoothly
- 10CFR851 issues
  - ◆ 851 interpretations
    - Occupational medical program
    - Health and safety plan
  - ◆ Blown-insulation would required respiratory protection
    - Testing was done on rock wool to determine fiber content
    - ACGIH identifies limits based on TWA of 1 fiber/cc
    - Fiber content well below limits therefore only dust masks required
  - ◆ 100% Fall protection – Very important
- Installation complete November 8, 2007



# Conclusion

- NFPA 25 IT&M program worked!
  - ◆ IT&M activities were performed on schedule
  - ◆ the problem was identified
- 10 CFR 851 was well managed
  - ◆ First major project at AMWTP that fell under 10 CFR 851
- Cooperation between ISIH and contractor was strong
  - ◆ Issues were worked through calmly and professionally (mostly)
- Air tests only performed for now (cold weather), hydro tests will be performed this summer
- The new sprinklers seem to be better than the old “O” ring style...time will tell



# Acknowledgements

- Bruce G. Campbell
- Mike Brooks
- Vernon Ball
- Bruce Stewart



# Questions?





HUGHES ASSOCIATES, INC.

**FIRE SCIENCE & ENGINEERING**



**Bechtel BWXT Idaho, LLC**

